

access road. The ground elevation contours within this area shall be restored to pre-construction elevations in accordance with Specific Condition No. 12.

7. Prior to construction, the permittee shall install "Caution: Construction Area" signs on land on either side of the spring outlet to alert boaters to the presence of the floating turbidity curtains at the project site. These signs shall be readily discernible to Department staff, remain in place during all construction activities, and shall be removed within 14 days of construction completion.

### **CONSTRUCTION CONDITIONS**

8. Side slopes, exposed and/or disturbed land surfaces shall be stabilized with shell fill and sand/clay fill as shown on the attached project drawing. The fill along the shoreline shall be placed at a slope no steeper than steeper than 2:1 (horizontal/vertical).
9. Any fill material used to stabilize the shoreline shall be clean fill and free of vegetative matter, trash, garbage, toxic or hazardous waste or any other unsuitable materials.
10. Wetland areas or waterbodies that are outside the specific limits of construction authorized by this permit must be protected from erosion, sedimentation, siltation, scouring, excess turbidity, and/or dewatering. There shall be no discharge in violation of the water quality standards in Chapter 62-302, F.A.C. Turbidity/erosion controls shall be installed prior to clearing, excavation or placement of fill material shall be maintained until construction is completed, disturbed areas are stabilized, and turbidity levels have fallen to less than ambient background. The turbidity and erosion control devices shall be removed within 14 days once these conditions are met.

If fill is to be placed below the existing water level, the permittee shall install floating turbidity curtains at the toe of the slope of the proposed fill area. Where fill is to be placed above the existing water level, the permittee shall install silt screens landward of the water's edge.

11. Construction activities shall not create turbidity in excess of the ambient water quality levels of the Outstanding Florida Waterbody. In the event of a visible plume outside the limits of the floating turbidity curtains and/or silt screens, the following measures shall be taken immediately by the permittee:
  - a. Immediately cease work contributing to the water quality violation.
  - b. Stabilize exposed soils contributing to the violation. Modify the work procedures responsible for the violation, install additional turbidity containment devices and repair non-functioning turbidity containment devices.
  - c. Notify the Department within 24 hours of the time the violation is first detected.