

17. Any collision with or injury to a manatee shall be reported immediately to the FWC Hotline at 1-888-404-3922. Collision and/or injury should also be reported to the U.S. Fish and Wildlife Service in Jacksonville (1-904-731-3336) for north Florida or Vero Beach (1-772-562-3909) for south Florida, and to FWC at ImperiledSpecies@myFWC.com
18. Temporary signs concerning manatees shall be posted prior to and during all in-water project activities. All signs are to be removed by the permittee upon completion of the project. Temporary signs that have already been approved for this use by the Florida Fish and Wildlife Conservation Commission (FWC) must be used (see MyFWC.com/manatee). One sign which reads *Caution: Boaters* must be posted. A second sign measuring at least 8 1/2" by 11" explaining the requirements for "Idle Speed/No Wake" and the shut down of in-water operations must be posted in a location prominently visible to all personnel engaged in water-related activities. Questions concerning these signs can be sent to the email address listed above.

CONSTRUCTION COMPLETION CONDITIONS (The permittee shall comply with the following conditions prior to the transfer to operation phase of the project. All documentation required below shall be included with the permittee's request to transfer the project to the operation phase [Form No. 62-343.900(7),F.A.C.])

19. The permittee shall submit two copies of signed, dated and sealed as-built drawings to the Department for review and approval within 30 days of completion of construction. The as-built drawings shall be based on the Department permitted construction drawings, which should be revised to reflect changes made during construction. Both the original design and constructed elevation must be clearly shown. The plans must be clearly labeled as "as-built" or "record" drawings. Surveyed dimensions and elevations required shall be verified and signed, dated and sealed by a Florida registered surveyor or engineer. *As-builts shall be submitted to the Department regardless of whether or not deviations are present.*

The information on the attached project drawing shall be verified on the as-built drawing from the engineered drawing signed and sealed by David W. Springstead, P.E. # 48229 on February 28, 2012.

20. Concurrently with the requirements of Specific Condition No. 19, within 30 days of construction completion, the permittee shall submit an as-built drawing of the ground elevation contours within the footprint of the temporary shell access road. These drawings shall demonstrate that the ground elevation contours have been restored to pre-construction conditions in accordance with Specific Conditions No. 6 and 12.
21. A "Time Zero" Monitoring Report shall be submitted within 30 days of completion of the restoration project and shall include the following:
 - a. Date the stabilization and plantings was completed;