

In general, reclamation will consist of returning the site to approximate preconstruction contours and elevations, replacement of the stockpiled topsoil and revegetation. The general processes are described below:

- Prior to mining the top 6 inches of topsoil will be removed and stockpiled nearby.
- The mined material will be returned to the mined area and restored to approximate preconstruction contours and elevations.
- The stockpiled topsoil will be replaced.
- The area will be revegetated with the appropriate native vegetation.

The Reclamation Plan detailing the activities that will take place will be submitted at a later date.