

Underground Work (trenching for wires from PV combiner boxes to inverters, inverter pad installation, trenching for medium voltage cables to interconnection equipment)



PV Panel Structure/Racking (driving of steel piles, installation of racking “tables”, installation of PV panels)



Electrical Work (connection of PV module wiring, combiner boxes, inverters, transformers, interconnection facilities)

