

activities are anticipated for the proposed project. Water trucks will be utilized as necessary for dust control.

### **OPERATION & MAINTENANCE**

The property owner will operate and maintain the stormwater management system as designed. The property owner will inspect the proposed setback/buffer areas once a week as necessary to assure no runoff flowing off-site. Any erosion will be restored to original design condition.

### **UTILITIES**

No water or wastewater utilities are proposed for the proposed project. Portable toilets will be provided on-site and maintained by the portable toilet company as necessary.

### **APPENDICES**

Appendix A – Location Map

Appendix B – USGS Quadrangle Map

Appendix C – Soils Map

Appendix D – Aerial Photograph

Appendix E – FEMA FIRM Map

Appendix F – Geotechnical Report

Appendix G – Property Ownership