

CLEARING AND GRADING NOTES:

1. ALL STRUCTURES, FENCES, CONCRETE, ASPHALT, AND UTILITIES NOT DESIGNATED TO BE

2. CONTRACTOR TO FILL ALL HOLES CREATED BY THE REMOVAL OF STRUCTURES, FENCES, AND TREES AND RETURN THOSE AREAS TO NATURAL GRADE.

3. THE CONTRACTOR SHALL COMPLY WITH APPLICABLE CODES, ORDINANCES, RULES, REGULATIONS AND LAWS OF LOCAL, MUNICIPAL, STATE OR FEDERAL AUTHORITIES HAVING JURISDICTION OVER THE PROJECT. ALL REQUIRED PERMITS OF A TEMPORARY NATURE SHALL BE OBTAINED FOR CONSTRUCTION OPERATIONS BY THE CONTRACTOR.

4. GRUBBING SHALL CONSIST OF COMPLETELY REMOVING ROOTS, STUMPS, TRASH AND OTHER DEBRIS FROM ALL GRADED AREAS SO THAT TOPSOIL IS FREE OF ROOTS AND DEBRIS.

5. ALL STUMPS, ROOTS, FOUNDATIONS AND PLANKING EMBEDDED IN THE GROUND SHALL BE REMOVED AND DISPOSED OF. PILING AND BUTTS OF UTILITY POLES SHALL BE REMOVED TO A MINIMUM DEPTH OF TWO FEET BELOW FINISH GRADE, WHICHEVER IS LOWER.

6. SURFACE ROCKS AND Boulders SHALL BE GRUBBED FROM THE SOIL AND REMOVED FROM THE SITE IF NOT SUITABLE AS RIP RAP.

7. ANY WORK PERTAINING TO UTILITY POLES SHALL COMPLY WITH THE REQUIREMENTS OF THE APPROPRIATE UTILITY.

8. THE DEBRIS RESULTING FROM THE CLEARING AND GRUBBING OPERATION SHALL BE HAULED TO A DISPOSAL SITE SECURED BY THE CONTRACTOR AND SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL REQUIREMENTS OF FEDERAL, STATE, COUNTY AND MUNICIPAL REGULATIONS. OR IN ANY KIND SHALL BE DEPOSITED IN ANY STREAM OR BODY OF WATER, OR IN ANY STREET OR ALLEY. NO DEBRIS SHALL BE DEPOSITED UPON ANY PRIVATE PROPERTY EXCEPT WITH WRITTEN CONSENT OF THE PROPERTY OWNER. A COPY OF WRITTEN CONSENT SHALL BE PROVIDED TO THE OWNER FOR PERMANENT RECORDS. IN NO CASE SHALL ANY MATERIAL OR DEBRIS BE LEFT ON THE PROJECT, SHOVED ONTO ABUTTING PRIVATE PROPERTIES OR BURIED ON THE PROJECT.

9. ALL GROWTH OF TREES, OTHER VEGETATION AND OBJECTABLE DEBRIS SHALL BE CLEARED AND GRUBBED FROM THE PROPOSED PAVED AREAS, BUILDING AREAS, LOCATION OF PROPOSED UTILITIES, AS WELL AS AREAS INDICATED TO BE GRADED ON THE PLANS.

10. ALL TREES, BRANCHES, VEGETATION AND DEBRIS SHALL BE DISPOSED OF IN A LEGAL MANNER ACCEPTABLE TO THE OWNER AND ENGINEER. BURNING PERMIT WILL BE OBTAINED BY THE CONTRACTOR AT OWN EXPENSE.

11. CONTRACTOR SHALL REMOVE TOPSOIL TO ITS ENTIRE DEPTH FROM ALL AREAS TO BE GRADED AND/OR FILLED. CONTRACTOR SHALL STOCKPILE OR REMOVE THE TOPSOIL FROM THE SITE AT OWNER'S DIRECTION.

12. ROADWAYS, EASEMENTS, AND SPECIAL FILL AREAS TO BE GRADED AND COMPACTED TO THE FINISHED SUBGRADE OR GRADES AS SHOWN ON THE PLANS.

13. IF UNSUITABLE MATERIAL IS ENCOUNTERED WITHIN THE ROADWAY, PARKING AREA OR ANY SPECIAL FILL AREA, IT SHALL BE REMOVED FROM THE ENTIRE PROPOSED PAVED AREA OR FILL AREA AND REPLACED WITH SELECT BACKFILL WHICH IS SUITABLE FOR ROADWAY (OR BUILDING SITE) CONSTRUCTION AS PER 'GDOT' REQUIREMENTS AND ANY SPECIAL REQUIREMENTS OF THE CITY, OWNER, ENGINEER, AND ANY AFFECTED GOVERNMENTAL AGENCIES.

14. FILL AND BACKFILL MATERIAL SHALL BE COMPACTED TO 98% STD. PROCTOR DENSITY AT OPTIMUM MOISTURE $\pm 2\%$ UNLESS SPECIFIED OTHERWISE ON THE PLAN.

15. ALL GRADING OPERATIONS SHALL BE DONE IN SUCH A MANNER SO AS TO PROVIDE POSITIVE DRAINAGE AT ALL TIMES.

16. ALL GRADES SHOWN ON PLANS ARE FINAL GRADE. GRADING CONTRACTOR SHALL COORDINATE WITH LANDSCAPE CONTRACTOR TO ENSURE POSITIVE DRAINAGE THROUGHOUT SITE.

17. CONTRACTOR SHALL INSTALL ALL STORM SEWER PIPE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.

18. ALL UNSUITABLE MATERIALS EXCAVATED/DISCOVERED AS A RESULT OF UTILITY INSTALLATION, STORM PIPE INSTALLATION, AND GRADING THAT ARE LOCATED INSIDE THE RIGHT-OF-WAY SHALL BE REMOVED AND GDOT APPROVED STRUCTURAL FILL USED TO BACKFILL.

GENERAL CONSTRUCTION NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH CITY OF VALDOSTA LAND DEVELOPMENT REGULATIONS.

2. WHILE WORKING WITHIN CITY OF VALDOSTA RIGHT OF WAY, EASEMENTS, OR ANY OTHER AREA WITHIN THE CONSTRUCTION LIMITS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEARING & GRUBBING AND THE REMOVAL OF ALL DEBRIS.

3. CONSTRUCTION SHALL HAVE ALL EROSION CONTROL MEASURES IN PLACE PRIOR TO CONSTRUCTION.

4. CONTRACTOR TO NOTIFY UTILITY PROTECTION CENTER A MINIMUM OF 72 HOURS PRIOR TO CONSTRUCTION.

5. CONTRACTOR TO VERIFY ALL HORIZONTAL & VERTICAL LOCATIONS OF ALL EXISTING AND PROPOSED STRUCTURES PRIOR TO CONSTRUCTION.

6. CONTRACTOR TO NOTIFY ENGINEER OF ANY CONFLICTS IN THE PLANS PRIOR TO AND DURING CONSTRUCTION. FAILURE TO NOTIFY ENGINEER WILL RESULT IN CONTRACTOR RESPONSIBILITY TO REPAIR AT OWN EXPENSE.

7. CONTRACTOR RESPONSIBLE FOR ALL DAMAGED UTILITIES DURING CONSTRUCTION.

8. PEDESTRIAN AND LOCAL TRAFFIC SHALL BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION. SAFETY DEVICES AND FLAGGERS WILL BE PROVIDED AT CONTRACTOR EXPENSE.

9. CONTRACTOR SHALL NOTIFY CITY OF VALDOSTA ENGINEERING DEPARTMENT A MINIMUM OF 24 HOURS PRIOR TO THE BEGINNING OF EACH PHASE OF CONSTRUCTION.

10. CONTRACTOR SHALL NOTIFY CITY OF VALDOSTA UTILITY DEPARTMENT A MINIMUM OF 24 HOURS PRIOR TO ANY CONNECTIONS TO THE CITY UTILITY SYSTEM.

11. CONTRACTOR TO PROVIDE ALL CONSTRUCTION STAKING.

12. A MINIMUM OF 18" OF VERTICAL AND 10' HORIZONTAL SEPARATION SHALL BE MAINTAINED BETWEEN ALL UTILITIES.

13. ALL EXTENSIONS AND ADDITIONS TO THE CITY OF VALDOSTA UTILITY SYSTEM WILL BE PERFORMED BY A GEORGIA LICENSED UTILITY CONTRACTOR.

14. ANY CROSS CONNECTION TO THE CITY OF VALDOSTA WATER SYSTEM IS PROHIBITED.

15. PRIOR TO PROJECT BIDDING, THE CONTRACTOR SHALL CLARIFY WITH THE OWNER/ENGINEER ANY DISCREPANCY THAT EXISTS BETWEEN THE REQUIREMENTS OF THE CONTRACT DOCUMENTS, CONSTRUCTION DRAWINGS, AND/OR PROJECT SPECIFICATIONS, REGARDLESS OF ANY LANGUAGE IN THE CONTRACT DOCUMENTS.

16. PRIOR TO PROJECT BIDDING, THE CONTRACTOR SHALL CLARIFY WITH THE OWNER/ENGINEER ANY DISCREPANCY THAT EXISTS BETWEEN THE REQUIREMENTS OF THE CONTRACT DOCUMENTS, CONSTRUCTION DRAWINGS, AND/OR PROJECT SPECIFICATIONS, REGARDLESS OF ANY LANGUAGE IN THE CONTRACT DOCUMENTS.

17. THE FINISHED SUBGRADE OR GRADES AS SHOWN ON THE PLANS.

18. ROADWAYS, EASEMENTS, AND SPECIAL FILL AREAS TO BE GRADED AND COMPACTED TO THE FINISHED SUBGRADE OR GRADES AS SHOWN ON THE PLANS.

19. ALL GRADING OPERATIONS SHALL BE DONE IN SUCH A MANNER SO AS TO PROVIDE POSITIVE DRAINAGE AT ALL TIMES.

20. ALL GRADES SHOWN ON PLANS ARE FINAL GRADE. GRADING CONTRACTOR SHALL COORDINATE WITH LANDSCAPE CONTRACTOR TO ENSURE POSITIVE DRAINAGE THROUGHOUT SITE.

21. CONTRACTOR SHALL INSTALL ALL STORM SEWER PIPE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.

22. ALL UNSUITABLE MATERIALS EXCAVATED/DISCOVERED AS A RESULT OF UTILITY INSTALLATION, STORM PIPE INSTALLATION, AND GRADING THAT ARE LOCATED INSIDE THE RIGHT-OF-WAY SHALL BE REMOVED AND GDOT APPROVED STRUCTURAL FILL USED TO BACKFILL.

UTILITY CONSTRUCTION NOTES:

1. THE CONTRACTOR SHALL PROVIDE AS-BUILTS AS REQUIRED BY THE MUNICIPALITY.

2. ALL SANITARY SEWER SERVICES SHALL BE TERMINATED AT THE R/W OR CONNECTED TO EXISTING SERVICE.

3. ALL WATER SERVICES SHALL BE TERMINATED AT THE R/W OR CONNECTED TO EXISTING SERVICE.

4. ALL WATER AND SEWER PIPE MATERIALS SHALL COMPLY WITH THE LATEST CODES AND SPECIFICATIONS OF THE LOCAL MUNICIPALITY OR UTILITY AUTHORITY.

5. THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING THE SUITABILITY OF PIPE MATERIALS WITH THE LOCAL MUNICIPALITY OR UTILITY AUTHORITY PRIOR TO PURCHASE.

6. THRUST BLOCKS SHALL BE INSTALLED AT ALL BENDS AND TEES PER DETAIL ON SHEET 59.

7. THE CONTRACTOR SHALL VERIFY VERTICAL LOCATION OF ALL UTILITIES, EXISTING & PROPOSED, PRIOR TO INSTALLATION TO ENSURE NO CONFLICTS WILL OCCUR BETWEEN SANITARY AND STORM SEWER MAINS.

8. THE CONTRACTOR SHALL PRESSURE TEST AND CHLORINATE THE WATER MAIN USING THE MINIMUM GUIDELINES PROVIDED BY THE LOCAL MUNICIPALITY GOVERNING THIS PROJECT.

9. SAMPLING POINTS SHALL BE INSTALLED EVERY 1200' ON THE WATER MAIN.

10. ALL ELECTRICAL AND TELEPHONE LINES TO BE SIZED PER ELECTRIC COMPANY AND TELEPHONE COMPANY STANDARDS TO ENSURE PROPER INSTALLATION.

11. THE CONTRACTOR SHALL VERIFY ALL EXISTING STORM STRUCTURE FLOW DIRECTIONS, HORIZONTAL AND VERTICAL LOCATIONS PRIOR TO BEGINNING CONSTRUCTION.

12. THE CONTRACTOR SHALL NOTIFY THE ENGINEER WHEN CONFLICTS OCCUR.

13. THE CONTRACTOR SHALL INSTALL ALL STORM SEWER PIPE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.

CLEARING AND GRADING NOTES:

1. ALL STRUCTURES, FENCES, CONCRETE, ASPHALT, AND UTILITIES NOT DESIGNATED TO BE

2. CONTRACTOR TO FILL ALL HOLES CREATED BY THE REMOVAL OF STRUCTURES, FENCES, AND TREES AND RETURN THOSE AREAS TO NATURAL GRADE.

3. THE CONTRACTOR SHALL COMPLY WITH APPLICABLE CODES, ORDINANCES, RULES, REGULATIONS AND LAWS OF LOCAL, MUNICIPAL, STATE OR FEDERAL AUTHORITIES HAVING JURISDICTION OVER THE PROJECT. ALL REQUIRED PERMITS OF A TEMPORARY NATURE SHALL BE OBTAINED FOR CONSTRUCTION OPERATIONS BY THE CONTRACTOR.

4. GRUBBING SHALL CONSIST OF COMPLETELY REMOVING ROOTS, STUMPS, TRASH AND OTHER DEBRIS FROM ALL GRADED AREAS SO THAT TOPSOIL IS FREE OF ROOTS AND DEBRIS.

5. ALL STUMPS, ROOTS, FOUNDATIONS AND PLANKING EMBEDDED IN THE GROUND SHALL BE REMOVED AND DISPOSED OF. PILING AND BUTTS OF UTILITY POLES SHALL BE REMOVED TO A MINIMUM DEPTH OF TWO FEET BELOW FINISH GRADE, WHICHEVER IS LOWER.

6. SURFACE ROCKS AND Boulders SHALL BE GRUBBED FROM THE SOIL AND REMOVED FROM THE SITE IF NOT SUITABLE AS RIP RAP.

7. ANY WORK PERTAINING TO UTILITY POLES SHALL COMPLY WITH THE REQUIREMENTS OF THE APPROPRIATE UTILITY.

8. THE DEBRIS RESULTING FROM THE CLEARING AND GRUBBING OPERATION SHALL BE HAULED TO A DISPOSAL SITE SECURED BY THE CONTRACTOR AND SHALL BE DISPOSED OF IN ACCORDANCE WITH ALL REQUIREMENTS OF FEDERAL, STATE, COUNTY AND MUNICIPAL REGULATIONS. OR IN ANY KIND SHALL BE DEPOSITED IN ANY STREAM OR BODY OF WATER, OR IN ANY STREET OR ALLEY. NO DEBRIS SHALL BE DEPOSITED UPON ANY PRIVATE PROPERTY EXCEPT WITH WRITTEN CONSENT OF THE PROPERTY OWNER. A COPY OF WRITTEN CONSENT SHALL BE PROVIDED TO THE OWNER FOR PERMANENT RECORDS. IN NO CASE SHALL ANY MATERIAL OR DEBRIS BE LEFT ON THE PROJECT, SHOVED ONTO ABUTTING PRIVATE PROPERTIES OR BURIED ON THE PROJECT.

GENERAL CONSTRUCTION NOTES:

1. ALL WORK SHALL BE IN ACCORDANCE WITH CITY OF VALDOSTA LAND DEVELOPMENT REGULATIONS.

2. WHILE WORKING WITHIN CITY OF VALDOSTA RIGHT OF WAY, EASEMENTS, OR ANY OTHER AREA WITHIN THE CONSTRUCTION LIMITS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEARING & GRUBBING AND THE REMOVAL OF ALL DEBRIS.

3. CONSTRUCTION SHALL HAVE ALL EROSION CONTROL MEASURES IN PLACE PRIOR TO CONSTRUCTION.

4. CONTRACTOR TO NOTIFY UTILITY PROTECTION CENTER A MINIMUM OF 72 HOURS PRIOR TO CONSTRUCTION.

5. CONTRACTOR TO VERIFY ALL HORIZONTAL & VERTICAL LOCATIONS OF ALL EXISTING AND PROPOSED STRUCTURES PRIOR TO CONSTRUCTION.

6. CONTRACTOR TO NOTIFY ENGINEER OF ANY CONFLICTS IN THE PLANS PRIOR TO AND DURING CONSTRUCTION. FAILURE TO NOTIFY ENGINEER WILL RESULT IN CONTRACTOR RESPONSIBILITY TO REPAIR AT OWN EXPENSE.

7. CONTRACTOR RESPONSIBLE FOR ALL DAMAGED UTILITIES DURING CONSTRUCTION.

8. PEDESTRIAN AND LOCAL TRAFFIC SHALL BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION. SAFETY DEVICES AND FLAGGERS WILL BE PROVIDED AT CONTRACTOR EXPENSE.

9. CONTRACTOR SHALL NOTIFY CITY OF VALDOSTA ENGINEERING DEPARTMENT A MINIMUM OF 24 HOURS PRIOR TO THE BEGINNING OF EACH PHASE OF CONSTRUCTION.

10. CONTRACTOR SHALL NOTIFY CITY OF VALDOSTA UTILITY DEPARTMENT A MINIMUM OF 24 HOURS PRIOR TO ANY CONNECTIONS TO THE CITY UTILITY SYSTEM.

11. CONTRACTOR TO PROVIDE ALL CONSTRUCTION STAKING.

12. A MINIMUM OF 18" OF VERTICAL AND 10' HORIZONTAL SEPARATION SHALL BE MAINTAINED BETWEEN ALL UTILITIES.

13. ALL EXTENSIONS AND ADDITIONS TO THE CITY OF VALDOSTA UTILITY SYSTEM WILL BE PERFORMED BY A GEORGIA LICENSED UTILITY CONTRACTOR.

14. ANY CROSS CONNECTION TO THE CITY OF VALDOSTA WATER SYSTEM IS PROHIBITED.

15. PRIOR TO PROJECT BIDDING, THE CONTRACTOR SHALL CLARIFY WITH THE OWNER/ENGINEER ANY DISCREPANCY THAT EXISTS BETWEEN THE REQUIREMENTS OF THE CONTRACT DOCUMENTS, CONSTRUCTION DRAWINGS, AND/OR PROJECT SPECIFICATIONS, REGARDLESS OF ANY LANGUAGE IN THE CONTRACT DOCUMENTS.

16. PRIOR TO PROJECT BIDDING, THE CONTRACTOR SHALL CLARIFY WITH THE OWNER/ENGINEER ANY DISCREPANCY THAT EXISTS BETWEEN THE REQUIREMENTS OF THE CONTRACT DOCUMENTS, CONSTRUCTION DRAWINGS, AND/OR PROJECT SPECIFICATIONS, REGARDLESS OF ANY LANGUAGE IN THE CONTRACT DOCUMENTS.

17. THE FINISHED SUBGRADE OR GRADES AS SHOWN ON THE PLANS.

18. ROADWAYS, EASEMENTS, AND SPECIAL FILL AREAS TO BE GRADED AND COMPACTED TO THE FINISHED SUBGRADE OR GRADES AS SHOWN ON THE PLANS.

19. ALL GRADING OPERATIONS SHALL BE DONE IN SUCH A MANNER SO AS TO PROVIDE POSITIVE DRAINAGE AT ALL TIMES.

20. ALL GRADES SHOWN ON PLANS ARE FINAL GRADE. GRADING CONTRACTOR SHALL COORDINATE WITH LANDSCAPE CONTRACTOR TO ENSURE POSITIVE DRAINAGE THROUGHOUT SITE.

21. CONTRACTOR SHALL INSTALL ALL STORM SEWER PIPE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.

22. ALL UNSUITABLE MATERIALS EXCAVATED/DISCOVERED AS A RESULT OF UTILITY INSTALLATION, STORM PIPE INSTALLATION, AND GRADING THAT ARE LOCATED INSIDE THE RIGHT-OF-WAY SHALL BE REMOVED AND GDOT APPROVED STRUCTURAL FILL USED TO BACKFILL.

SHEET NO.	DRAWING NO.	DESCRIPTION
1	1-001	COVER
2-3	2-001 - 2-002	INDEX / OVERALL PROJECT
4	5-001	TYPICAL SECTIONS
5-8	11-001 - 11-004	EXISTING SURVEY
9-13	13-001 - 13-005	CONSTRUCTION PLAN
14-21	15-001 - 15-008	MAINLINE PROFILE
22-27	22-001 - 22-006	DRAINAGE PROFILES
28-42	23-001 - 23-015	CROSS SECTIONS
43-49	24-001 - 24-007	UTILITY PLANS
50-53	26-001 - 26-004	SIGNAL & MARKING PLAN
54-58	27-000 - 27-004	DETAILS
59-65	41-001 - 41-003	ESPC DETAILS
66-68	51-001 - 51-003	ESPC PLAN
69-74	54-001 - 54-009	

UTILITY CONSTRUCTION NOTES:

1. THE CONTRACTOR SHALL PROVIDE AS-BUILTS AS REQUIRED BY THE MUNICIPALITY.

2. ALL SANITARY SEWER SERVICES SHALL BE TERMINATED AT THE R/W OR CONNECTED TO EXISTING SERVICE.

3. ALL WATER SERVICES SHALL BE TERMINATED AT THE R/W OR CONNECTED TO EXISTING SERVICE.

4. ALL WATER AND SEWER PIPE MATERIALS SHALL COMPLY WITH THE LATEST CODES AND SPECIFICATIONS OF THE LOCAL MUNICIPALITY OR UTILITY AUTHORITY.

5. THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING THE SUITABILITY OF PIPE MATERIALS WITH THE LOCAL MUNICIPALITY OR UTILITY AUTHORITY PRIOR TO PURCHASE.

6. THRUST BLOCKS SHALL BE INSTALLED AT ALL BENDS AND TEES PER DETAIL ON SHEET 59.

7. THE CONTRACTOR SHALL VERIFY VERTICAL LOCATION OF ALL UTILITIES, EXISTING & PROPOSED, PRIOR TO INSTALLATION TO ENSURE NO CONFLICTS WILL OCCUR BETWEEN SANITARY AND STORM SEWER MAINS.

8. THE CONTRACTOR SHALL PRESSURE TEST AND CHLORINATE THE WATER MAIN USING THE MINIMUM GUIDELINES PROVIDED BY THE LOCAL MUNICIPALITY GOVERNING THIS PROJECT.

9. SAMPLING POINTS SHALL BE INSTALLED EVERY 1200' ON THE WATER MAIN.

10. ALL ELECTRICAL AND TELEPHONE LINES TO BE SIZED PER ELECTRIC COMPANY AND TELEPHONE COMPANY STANDARDS TO ENSURE PROPER INSTALLATION.

11. THE CONTRACTOR SHALL VERIFY ALL EXISTING STORM STRUCTURE FLOW DIRECTIONS, HORIZONTAL AND VERTICAL LOCATIONS PRIOR TO BEGINNING CONSTRUCTION.

12. THE CONTRACTOR SHALL NOTIFY THE ENGINEER WHEN CONFLICTS OCCUR.

13. THE CONTRACTOR SHALL INSTALL ALL STORM SEWER PIPE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.

14. ALL UNSUITABLE MATERIALS EXCAVATED/DISCOVERED AS A RESULT OF UTILITY INSTALLATION, STORM PIPE INSTALLATION, AND GRADING THAT ARE LOCATED INSIDE THE RIGHT-OF-WAY SHALL BE REMOVED AND GDOT APPROVED STRUCTURAL FILL USED TO BACKFILL.

15. ALL GRADING OPERATIONS SHALL BE DONE IN SUCH A MANNER SO AS TO PROVIDE POSITIVE DRAINAGE AT ALL TIMES.

16. ALL GRADES SHOWN ON PLANS ARE FINAL GRADE. GRADING CONTRACTOR SHALL COORDINATE WITH LANDSCAPE CONTRACTOR TO ENSURE POSITIVE DRAINAGE THROUGHOUT SITE.

17. CONTRACTOR SHALL INSTALL ALL STORM SEWER PIPE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.

18. ALL UNSUITABLE MATERIALS EXCAVATED/DISCOVERED AS A RESULT OF UTILITY INSTALLATION, STORM PIPE INSTALLATION, AND GRADING THAT ARE LOCATED INSIDE THE RIGHT-OF-WAY SHALL BE REMOVED AND GDOT APPROVED STRUCTURAL FILL USED TO BACKFILL.



GA CORP# 0419089
FL CORP# P0400002135
P.O. Box 2830
3998 Inver Plummer Road
Valdosta, GA 31504
Telephone: 229-253-0000
Fax: 229-253-1612
E-mail: lea@leae-epc.com

COVER
INDEX / OVERALL PROJECT
TYPICAL SECTIONS
EXISTING SURVEY
CONSTRUCTION PLAN
MAINLINE PROFILE
DRAINAGE PROFILES
CROSS SECTIONS
UTILITY PLANS
SIGNAL & MARKING PLAN
DETAILS
ESPC DETAILS
ESPC PLAN

OLD CLAYVILLE ROAD WIDENING
PI#0016285
LAND LOT 64 & 29 OF THE
CITY OF VALDOSTA
LOWNDES COUNTY
STATE OF GEORGIA

REVISIONS	DATE	DESCRIPTION

Know what's below.
Call before you dig.
IF YOU DIG GEORGIA... CALL US FIRST!
UTILITIES PROTECTION CENTER
IT'S THE LAW
www.gaprc.com

SCALE: M.T.S.
DESIGNED BY: DEA
CHECKED BY: MCM
SUBMITTAL DATE: 03-24-23
JOB NO. 0026-40
THESE DRAWINGS ARE THE PROPERTY OF LEA AND MAY NOT BE REPRODUCED OR
USED WITHOUT PERMISSION AND CREDIT.
© LEA, PC 2023

INDEX
(SHEET 1 OF 1)
2-001
2 OF 74 SHEETS

2-001
2 OF 74 SHEETS