

Emergency Event:	<b>WW-3 WASTEWATER PUMP STATION FAILURE</b>
Emergency Trigger:	<ul style="list-style-type: none"> <li>• SCADA Alarm</li> <li>• Power Outage</li> <li>• Loss of flow to WPCP</li> <li>• Visible evidence of leaking wastewater</li> <li>• Public complaint</li> </ul>
Risks:	<ul style="list-style-type: none"> <li>• Loss of flow to WPCP</li> <li>• Possible Sanitary Sewer Overflow (SSO)/Spill</li> <li>• Contamination / Health</li> <li>• Environmental / Property Damage</li> </ul>

**Actions Required:**

- Investigate extent and cause of failure
- Make necessary repairs utilizing approved methods and procedures
- If necessary, implement temporary bypassing.
- If failure results in sewage overflow/spill, see procedures in SOP: Emergency Response to Sanitary Sewer Overflow/Spill

**Internal Contacts:**

- Utilities Director (ER Lead)
- Asst. Utilities Director (Alternate ER Lead)
- ER/Assessment Team
- Fire Department
- City Engineer
- Public Information Officer
- Central Warehouse
- City Manager/Asst. City Manager

**External Contacts:**

EPD  
Affected Customers

**Follow Up Actions Required:**

- Update maintenance records with details of the actions.
- Written report.
- Written report to EPD, if necessary.