



VIA EMAIL

Construction Layout/Stakeout Plans (4)
 Mainline Roadway Plan and Profile Sheets (7)
 Intersection Plan and Profiles (2)
 Special Grading Drawings (Sediment/Detention Basins, etc.) (2)
 Drainage Area Map (1)
 Drainage Plan and Profiles (4)
 Cross-Sections (6)
 Signing and Marking Plans and Details (5)
 Signal Plans (4)
 Construction Details (6)
 Erosion, Sediment, and Pollution Control Plans (ESPC) Cover Sheet (1)
 ESPC Narrative Plan (1)
 ESPC Initial/Intermediate/Final Plan for longitudinal project (7)
 ESPC Watershed Map and Site Monitoring Location (1)
 ESPC Construction Details (4)
 GDOT ROW Plans (8)

3. Environmental Services Lump Sum: \$55,500
 LEA will provide an aquatic resource delineation for the project corridor. LEA will prepare and submit the appropriate USACE and Georgia EPD permit applications for impacts required to construct the improvements. ESPC plans will also be provided per GSWCC and EPD requirements. The application for the NPDES permit will be completed via the online GEOS portal and ESPC plans will be submitted to EPD for land disturbance approval. A culvert analysis will also be completed for the major drainage crossing. No FEMA coordination is anticipated for this project.
4. Bidding Phase Lump Sum: \$15,000
 LEA will assist the City with putting together the bid documents, attending the pre-bid meeting, and responding to RFIs during the bid process.
5. Construction Administration
 LEA will assist the City as needed during the construction phase on an hourly basis. A lump sum for these services can be determined once the design is finalized and the detailed scope of construction administration is defined.